

REVISED 9/17/2018

SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL	UNIT PRICE	AMOUNT
20200100	EARTH EXCAVATION	CU YD	285.0		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	165.0		
25000210	SEEDING, CLASS 2A	ACRE	0.1		
25000310	SEEDING, CLASS 4 (MODIFIED)*	ACRE	0.1		
25000322	SEEDING, CLASS 5A	ACRE	0.1		
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	400.0		
35100110	AGGREGATE BASE COURSE, TYPE A	CU YD	176.0		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	6920.0		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	90.0		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1.0		
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	1.0		
A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	2.0		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	13.0		

NOTE: WORK SHALL BE IN ACCORDANCE WITH THE APRIL 2016 ILLINOIS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

Total	
-------	--

SEEDING CLASS 4 SHALL BE MODIFIED TO EXCLUDE PERENNIAL RYEGRASS. ALL OTHER SEEDS SHALL BE PER THE STANDARD SPECIFICATION.

BIDDER CAN USE THIS FORM FOR SUBMISSION OF UNIT PRICES. SIMILAR FORMS WILL BE ACCEPTED.